



CSI SECTION 03 60 00 – GROUTING
03 62 00 – NON-SHRINK GROUTING
03 62 13 – NON-METALLIC NON-SHRINK GROUTING

Non-Metallic, Multi-Purpose, Cementitious, Non-Shrink Grout

EDITOR NOTE: The following guideline specification has been prepared to assist architects and design professionals in the preparation of project master specifications. It is intended for use by qualified design professionals and is not intended to be used verbatim. Appropriate modifications to meet specific project requirements are required. Make appropriate [selections] where options are provided and delete items that are not applicable to the project. Contact info@cmacement.com for additional information or project specification assistance.

PART 1 - GENERAL

1.1 SECTION INCLUDES

Supply and installation of a non-shrink, non-metallic ultra rapid setting, high strength cementitious grout for slab bedding of precast concrete roadway panels. Voids under sub-grade and precast concrete panels fill load transfer slots and longitudinal joints as product exhibits no bleeding and high pumpability with 8 inches placement thickness.

1.2 RELATED SECTIONS

- [A. Section 03 01 00 - Maintenance of Concrete
- [B. Section 03 01 40 - Maintenance of Precast Concrete
- [C. Section 03 01 50 - Maintenance of Cast Decks and Underlayment
- [D. Section 03 01 60 - Maintenance of Grouting
- [E. Section 03 01 80 - Maintenance of Concrete Cutting and Boring
- [F. Section 03 30 00 - Cast-in-Place Concrete
- [G. Section 03 40 00 - Precast Concrete
- [H. Section 03 50 00 - Cast Decks and Underlayment
- [I. Section 03 54 16 - Hydraulic Cement Underlayment
- [J. Section 03 70 00 - Mass Concrete
- [K. Section 04 01 00 - Maintenance of Masonry
- [L. Section 04 20 00 - Unit Masonry
- [M. Section 05 05 19 - Post-Installed Concrete Anchors

1.3 REFERENCES

- A. ASTM C78 Test Method for Flexural Strength of Concrete
- B. ASTM C109 Standard Test Method for Compressive Strength of Hydraulic Cement Mortars
- C. ASTM C150 Standard Specification for Portland Cement
- D. ASTM C191 Test Method for Time of Setting of Hydraulic Cement by Vicat Needle
- E. ASTM C266 Standard Test Method for Time of Setting of Hydraulic-Cement Paste by Gillmore Needles
- F. ASTM C348 Standard Test Method for Flexural Strength of Hydraulic-Cement Mortars
- G. ASTM C827 Test Method for Change in Height at Early Ages of Cylindrical Specimens from



	Cementitious Mixtures
H. ASTM C939	Test Method for Flow of Grout for Preplaced Aggregate Concrete (Flow Cone Method)
I. ASTM C1090	Standard Test Method for Measuring Changes in Height of Cylindrical Specimens of Hydraulic-Cement Grout
J. ASTM C1107	Standard Specification for Packaged Dry, Hydraulic-Cement Grout (Non-Shrink)
K. ACI 301	Specification for Structural Concrete
L. ACI 318	Building Code Requirements for Structural Concrete
M. CRD-C 621	Corps of Engineers Specification for Non-Shrink Grout
N. ASTM C928	Standard Specification for Packaged, Dry, Rapid Hardening Cementitious Material for Concrete Repairs
O. CT 417	Methods for Testing Soils and Waters for Sulfates by weight %
P. CT 422	Methods for Testing Soils and Waters for Chloride by weight %
Q. CT 551	Methods of Test for the Suitability of Materials for Overlaying and Repair of Portland Cement Concrete Pavement and Structures

1.1 SUBMITTALS

- A. General: Submit samples and manufacturer's product data sheets, installation instructions, etc. in accordance with Division 01 General Requirements Submittal Section.
- B. Test Data: Submit qualified testing data that confirms compliance with specified performance requirements.

1.2 QUALITY ASSURANCE

- A. Qualifications:
 - 1. Manufacturer:
 - a. Must have marketed non-shrink grouting materials in the United States for at least five years and must have completed projects of the same general scope and complexity.
 - b. Grout and complementary admixture materials must be manufactured by or approved for use by CC Products Inc. (714- 523-2006, www.cmaxcement.com) and distributed by the same or an authorized CMAX Cement/ CC Products Inc. dealer.
 - 2. Applicator:
 - a. Must be experienced and competent in installation of non-shrink grouting materials and provide evidence of a minimum of five years' experience in work similar in size and scope to that required by this section.

1.3 DELIVERY, STORAGE, AND HANDLING

- A. Delivery: Deliver products in original, unopened, undamaged packaging with manufacturer's identification (i.e., brand logo, product name, weight of packaged unit, lot number).
- B. Storage: Store products in a dry location, covered, out of direct sunlight, off the ground, and protected from moisture. Maintain storage temperature required by the manufacturer. Keep materials dry until used. Handling: Handle products in accordance with manufacturer's published recommendations.

1.4 SITE / ENVIRONMENTAL CONDITIONS

- A. Temperature: Maintain ambient and surface temperatures between 45°F (7°C) to 90°F (32°C). Do not apply grout materials if ambient temperature falls below 45°F (7°C) within 24 hours of application. Protect grout from uneven and excessive evaporation during dry weather, windy conditions and strong blasts of dry air.
- B. Inclement Weather: Do not apply grout materials during inclement weather unless appropriate



protection is employed.

- C. Sunlight Exposure: Avoid, whenever possible, installation of grout materials in direct sunlight which could adversely affect aesthetics.
- D. Substrate: Prior to installation, the substrates must be inspected for surface contamination or other conditions that may adversely affect the performance of the grouting materials and be free of residual moisture.

1.5 COORDINATION AND SCHEDULING

- A. Coordinate installation of grout materials with all other trades to avoid impeding other construction.
- B. Sufficient manpower must be provided to ensure continuous application and timely finishing.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Basis of Design: CMAX Cement / CC Products Inc., 2400 E. Katella Avenue, Suite 800, Anaheim, CA 92801 (714- 523-2006, www.cmaxcement.com).
- B. Components: Obtain grout and admixture materials manufactured by CMAX Cement/ CC Products Inc. from authorized distributors. No substitutions or additions of other materials are permitted without prior written permission from the manufacturer for this project.

2.2 MATERIALS

- A. Non-Shrink, Cementitious Grout
 - 1. CMAX Construction Grout: a high-quality blend of portland cement, non-shrink additives, and specialty sand pre-packaged to produce a durable non-shrink, cementitious grout with maximum mix design versatility. Mix with water to any consistency, from damp pack to fluid. Suitable for structural and non-structural applications.
 - 2. Additives and admixture materials must be approved for use by CMAX Cement / CC Products Inc. prior to use. (714-523-2006, www.cmaxcement.com)
- A. Water: Clean, potable water free of deleterious amounts of silt and dissolved salts.

2.3 MATERIAL PROPERTIES

- A. Non-Shrink, Cementitious Grout
 - 1. Compliance with: ASTM C1107, Grades A, B, C, ASTM C1090, ASTM C827, Corps of Engineers CRD-C 621.
 - 2. Minimum performance requirements:

Set Time (ASTM C266 Modified)	<u>At 73° F</u> Initial Set 25 min. Final Set 35 min.	<u>At 45° F</u> Initial Set 35 min Final Set 45 min.
Compressive Strength (ASTM C109 Modified)	<u>At 73° F</u> 1 Hour 2500 psi (17.2 MPa) 7 Day 7600 psi. (52.4 MPa)	<u>At 45° F</u> 1 Hour 2000 psi. (14.0 MPa) 7Day 6000 psi. (41.4 MPa)
Post-Hardened Height Expansion (ASTM C1090) 1,3,7, and 28 days Result: 0 to 0.2%	Pre-Hardened Height Expansion (ASTM C827) 1,3,7, and 28 days Result: 0 to 1%	Bond Strength @ 24 hours CT 551 Result: 300 lbs.
Total Chloride Content, by % CT 422 Result:0.05%	Total Sulphates Content by % CT 417 Result: 5.0%	

2.4 RELATED MATERIALS

- A. Admixtures: Do not add additional dry materials such as cement, sand, additives or admixtures. Mix only with water. All additives and admixture materials must be approved for use by CMAX Cement/ CC Products Inc. prior to use. (714-523-2006, www.cmaxcement.com)
- B. Dry 3/8 pea gravel may be added for placements with thicknesses over 2 inches. Add at a rate of 25 lbs. per 50 lb. bag of grout.
- C. Consult with a qualified CMAX Cement Technical Representative prior to the project if grout will be pumped, mixed in a ready-mix truck, used with pea gravel, used at temperature extremes, installed less than 1/2-inch-thick or over 6 inches thick, or when unusual job site conditions are anticipated. (800-929-3030, www.CMAXcement.com)
- D. Concrete Cleaner: Citrus-based concrete cleaner to clean and strip dirt, grease and laitance from surfaces to receive grout.
- E. Curing: Prevent rapid water loss from grout during the first 48 hours by use of
 - 1. Wet Burlap Method
 - 2. Curing Compound compliant with ASTM C309 Type I, Class B.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify project site conditions under provisions of Section 01 00 00.
- B. Compliance: Comply with manufacturer's instructions for installation of grouting materials.
- C. Coordinate installation with adjacent work to ensure proper sequencing of construction.
- D. Protect adjacent and surrounding surfaces not specified to receive grout with necessary means to ensure protection against overspray, water or other harmful debris.
- E. Advise Contractor of discrepancies preventing proper installation of grouting materials. Do not



proceed with the work until unsatisfactory conditions are corrected.

3.2 PREPARATION

- A. Mechanically roughen surfaces and remove all loose, unsound, contaminated material.
- B. Bonding surfaces must be clean, sound, and free from any materials that may inhibit bond such as oil, dirt, asphalt, sealing compounds, acids, wax and loose dust and debris.
- C. Reinforcing steel must be free from rust and all other materials that may inhibit bond.

EDITOR NOTE: Add special requirements related to the replacement of reinforcement that has lost too much cross-sectional area.

- D. Thoroughly saturate the area to receive grout with water for a minimum of 4 hours, preferably 24 hours, before grout placement. Remove any standing water before material placement.
- E. Minimum substrate temperature must be 45°F (7°C) and maximum substrate temperature 90°F (32°C).
- F. For formed grouting applications, construct watertight, non-absorbent forms. Build forms 1 inch higher than the bottom of the plate and 1 to 3 inches between the side of the plate and the form.
- G. Joints must be sealed with foam, caulk or putty.
- H. Provide vent holes to avoid air entrapment.
- I. Provide a head placement of a 45-degree angle to facilitate placement for grout pour.

3.3 MIXING

- A. CMAX® S: Comply with manufacturer's printed instructions and the following:
 - 1. Organize installation personnel and equipment before mixing begins.
 - 2. Use water based on the following guidelines and consistencies per 50 lb. bag of grout:
 - a. Plastic5.0 quarts
 - b. Flowable5.5 quarts
 - c. Fluid5.75 quarts
 - 3. Adjust water to achieve the desired flow consistency. Do not exceed 6.25 quarts of water per 50 lb. bag. Gauge fluid consistency within 25-35 seconds per ASTM C939 Flow Cone Method.
 - 4. If dry 3/8 pea gravel is used, start a flowable consistency at 5.5 quarts and add water to achieve desired flow consistency. Do not exceed total water of 6.25 quarts per 50 lb. bag. Too much water may induce bleeding and segregation.
 - 5. Add water to the mixing container. While mixing in a power driven mechanical mixer, such as a mechanical mortar mixer or drill mounted mixer, add CMAX Construction Grout.
 - 6. All additives and admixture materials must be approved for use by CMAX Cement Manufacturing Corp. prior to use. (800-929-3030, www.CMAXcement.com)
 - 7. Never mix by hand. Do not re-temper, add water, or remix after the grout stiffens. Grout that stiffens before use must be discarded.

3.4 APPLICATION

- A. CMAX® SBG: Comply with manufacturer's printed instructions and the following:
 - 1. Verify that all substrates and ambient temperatures are between 45°F (7°C) to 90°F (32°C) and will remain within range until the grout has reached final set.



2. Place grout into forms continuously by pump or pouring in one placement. Fill all areas to be grouted and stay in contact with load bearing areas.
3. Limit the amount of vibration during grout placement to prevent segregation. All machinery near grout placement should be shut down for 24 hours after placement.
4. Remove forms once the grout has achieved final set.

3.5 CURING

- A. Apply curing compound in accordance with ASTM C309 immediately after finishing or upon final set. Apply curing compound to all exposed grout surfaces after forms are removed.

OPTION: Wet cure grout placement with clean, potable water for 3 full days

3.6 CLEAN-UP

- A. Remove and legally dispose of grouting debris material from job site.
- B. Clean excess material from surrounding areas and all tools immediately, before material cures. If materials have cured, remove using mechanical methods that will not damage the substrate.
- C. Clean adjacent surfaces as needed using materials and methods recommended by the manufacturer of the material being cleaned. Remove and replace work that cannot be cleaned to the satisfaction of the Project Designer/Owner.

END OF SECTION

Rev. July 17,2018

This sample guideline specification is intended for use by a qualified design professional. The sample guideline specification is not intended to be used verbatim as an actual specification without appropriate modifications for the specific project requirements.